

DATA ITEM DESCRIPTION

Title: Recovered Chemical Warfare Materiel Safety Submission (CSS)

Number: OE-070.01

Approval Date: 20021001

AMSC Number:

Limitation:

DTIC Applicable: No

GIDEP Applicable: No

Office of Primary Responsibility: CEHNC-OE-CX

Applicable Forms:

Use/Relationship: The Recovered Chemical Warfare Materiel (RCWM) Safety Submission (CSS) will be used to provide RCWM response action safety criteria for approval by an appropriate DOD Element. This Data Item Description (DID) incorporates guidance contained in OASA (I, L &E) Memorandum, SUBJECT: Interim Guidance for Biological Warfare Materiel (BWM) and Non-Stockpile Chemical Warfare Materiel (CWM) Response Activities, 5 Sep 1997, AR and DA PAM 385-61, AR and DA PAM 385-64, AR 50-6, and EP 75-1-3.

Requirements: The Contractor shall, when required by the Government, submit a CSS, which describes the safety criteria to be employed during RCWM response operations. The CSS shall be printed double-sided, formatted in Word, and shall be prepared using the format in Attachment A. Chapters will be as indicated in the outline for each major area. If a specific chapter or subject is not applicable to the project site, enter a "NA" after the chapter heading.

1. Outline for CSS (Refer to Attachment A).
2. End of DID OE-070.01.

DID OE-070.01

Attachment A Outline for RCWM Safety Submission (CSS) General Guidelines

- 1.0 It is intended for this document to be a “stand-alone” document from the Work Plan (WP) and the Site Safety and Health Plan (SSHP) and other supplemental plans for the project site.
- 2.0 This plan is built on the WP and SSHP and supplemental plans, so those plans must be complete before the CSS can be completed.
- 3.0 The overall length of the plan should not exceed 100 single-sided pages.
- 4.0 It is intended to provide those reviewing and approving agencies the necessary technical information, as required in the DA Interim Guidance of 1997. This outline has been agreed to by CEHNC and USATCES. No substantive changes will be made without the approval of the OE-CX.
- 5.0 Document control is positively essential during the drafting, editing, and publishing of this CSS. Each page must have a footer that identifies the document, either original date or date of the latest change. Additionally, a sheet shall be inserted into the front of the document that specifies the latest dates and changes. All changes to the original document will leave the bars in the outside margins to identify change locations throughout the document.
- 6.0 It is intended for this document to include the necessary information required for an Explosive Safety Submission (ESS) as well, should it be necessary for the conduct of site operations for the RCWM activities.

DID OE-070.01

Attachment A Outline for RCWM Safety Submission (CSS)

Page/paragraph numbers are intended as a guide only, to indicate the length and brevity of paragraphs to cover specific topics.

| | |
|---|------|
| ES1.0 Executive Summary | ES-1 |
| ES1.1 Introduction brief description of why the project authorization | ES-1 |
| ES1.2 Brief description of what OE items are expected, includes RCWM | ES-1 |
| ES1.3 Brief description of ABPs | ES-1 |
| ES2.0 Brief description of site history and background | ES-2 |
| ES3.0 Brief synopsis of site operations | ES-2 |
| ES3.1 Intrusive operations (brief paragraph on the activity covering; reacquisition of anomalies, use of UXO personnel, use of engineering controls or evacuation, use of fragmentation distances, use of NOSE distances) | ES-2 |
| ES3.2 Brief description of the MPM | ES-3 |
| ES3.3 Brief description of the MCE | ES-3 |
| ES3.4 Brief description of discovery actions for: conventional ordnance items, suspect ordnance items, is EOD required, if suspect RCWM TEU does assessment, if preliminary assessment is RCWM then packaging by TEU, transportation to IHF by TEU, subsequent assessment by TEU | ES-4 |
| ES4.0 Brief description of air monitoring for RCWM agents; using MINICAMs, for agents (name them), DAAMs, OP-FTIR, sentence on appropriate personal protective equipment, dependent upon air monitoring results. | ES-4 |
| ES4.1 Brief description of actions to be taken in the event of a MINICAMs ring-off or discovery of RCWM | ES-4 |
| ES5.0 Chemical Data, Laboratory, and Field Work Sampling | ES-4 |
| ES5.1 Brief paragraph on the types of samples that will be taken on site; surficial sampling, subsurface soil, pit characterization, soil disposal, aqueous investigative waste, decontamination water, Investigative Derived Waste (IDW) | ES-4 |
| ES5.2 Brief paragraph on what CWA is expected and the applicable ABPs and how and who will be doing the analysis | ES-5 |
| ES5.3 Brief paragraph on the sampling of the HTW and the sampling parameters including EPA TCL for volatile organic compounds (VOCs), semi-volatile organic (SVOCs) compounds and metals and disposal parameters. Disposal parameters refer to the TCLP listed VOCs, SVOCs, and metals. Who will be doing the HTW analysis? | ES-5 |
| ES6.0 Monitoring and Disposal. Statement; the Work Plan describes the monitoring and disposal procedures for Non-RCWM intact containers, scrap, and soil encountered during the intrusive operations | ES-5 |
| ES7.0 Site Usage after cleanup, brief statement as to projected site usage after cleanup | ES-5 |

DID OE-070.01

Attachment A Outline for RCWM Safety Submission (CSS)

Table of Contents

| | |
|---|------|
| 1.0 Introduction | |
| 1.1 Conventional Ordnance Handling Plan | 1-1 |
| 1.1.1 Conventional UXO Types | 1-1 |
| 1.1.2 On-Site Disposal Operations | 1-1 |
| 1.1.3 Explosives Siting Plan Requirements | 1-2 |
| 1.1.4 Explosives Management Plan Requirements | 1-2 |
| 1.2 Summary of Actions (brief paragraph describing the below, list personnel limits for each activity) | 1-4 |
| 1.2.1 CWM | 1-4 |
| 1.2.2 Conventional UXO | 1-4 |
| 1.2.3 HTW | 1-5 |
| 1.2.4 Heavy Equipment | 1-6 |
| 1.2.5 Activity Hazard Analysis for RCWM and Explosives-related tasks (all others will be located within the SSHP) | 1-6 |
| 1.3 Organizational Responsibilities | 1-7 |
| 1.3.1 UXO Contractor | 1-7 |
| 1.3.2 HTW Contractor | 1-7 |
| 1.3.3 ECBC | 1-7 |
| 1.3.4 TEU | 1-7 |
| 1.3.5 Industrial Air Monitoring | 1-7 |
| 1.3.6 CEHNC (include Chemical Event Reporting and Safety Oversight of Site Operations) | 1-8 |
| 1.3.7 Corps District | 1-8 |
| 1.4 Most Probable Munition (MPM) and Maximum Credible Event (MCE) | 1-9 |
| 1.4.1 Fragmentation Distance of MPM | 1-9 |
| 1.4.2 No Significant Effects (NOSE) Distance for MCE (provided by CEHNC) | 1-9 |
| 1.4.3 Interim Holding Facility | 1-9 |
| 1.5 Maps and Drawings | 1-10 |
| 1.5.1 Fragmentation Zones (QD Arcs) | 1-10 |
| 1.5.2 NOSE (Public Withdrawal Distance) | 1-10 |
| 1.5.3 Public Access Exclusion Distance (PAED) (1% Lethality) | 1-11 |
| 1.5.4 Installation Boundaries | 1-11 |
| 1.5.5 Explosive Storage Locations | 1-11 |
| 1.5.6 Interim Holding Facility (IHF) Location | 1-11 |
| 1.5.7 Overall Site Map | 1-12 |
| 1.5.8 Predetermined UXO Disposal Locations for Safe-To-Move UXO | 1-12 |
| 2.0 Sampling Plan Summary | 2-1 |
| 2.1 Introduction | 2-1 |
| 2.2 Soil Sampling | 2-1 |
| 2.2.1 Pit Characterization Sampling | 2-1 |
| 2.2.2 Soil Disposal Sampling | 2-2 |
| 2.3 Aqueous Sampling | 2-3 |
| 2.4 Scrap and Non-RCWM Intact Container Sampling | 2-3 |
| 2.5 Backfill Sampling | 2-3 |
| 2.6 3-X Sampling | 2-4 |
| 3.0 Air Monitoring Plan | 3-1 |
| 3.1 HTW | 3-1 |
| 3.2 RCWM | 3-1 |
| 3.3 Environmental/Industrial | 3-1 |

DID OE-070.01

Attachment A Outline for RCWM Safety Submission (CSS)

| | |
|--|-----|
| 4.0 Personal Protective Equipment and Decontamination Summary | 4-1 |
| 4.1 Personal Protective Equipment (PPE) Summary | 4-1 |
| 4.1.1 General Requirements | 4-1 |
| 4.1.2 Task Specific Levels of PPE | 4-1 |
| 4.2 Personal Decontamination Procedures | 4-2 |
| 4.2.1 General Decontamination Procedures | 4-2 |
| 4.2.2 Specific Decontamination Procedures | 4-2 |
| 4.3 Equipment Decontamination Procedures | 4-3 |
| 4.3.1 General Decontamination Procedures | 4-3 |
| 4.3.2 Specific Decontamination Procedures | 4-3 |
| | |
| 5.0 Medical Support Summary | 5-1 |
| | |
| 6.0 Public Protection Plan Summary | 6-1 |
| 6.1 Public Notifications | 6-1 |
| 6.2 Emergency Operations | 6-1 |
| 6.3 Downwind Hazard Modeling (D2PC) Calculations | 6-1 |
| | |
| 7.0 Interim Holding Facility Siting Plan Summary | 7-1 |
| 7.1 Introduction | 7-1 |
| 7.2 IHF Container Description | 7-1 |
| 7.2.1 Location and Layout | 7-2 |
| 7.3 IHF Siting Requirements | 7-3 |
| 7.3.1 Public Access Exclusion Distance and 1% Lethality Distance | 7-3 |
| 7.3.2 Inhabited Building Distance (IBD) | 7-3 |
| 7.3.3 Net Explosive Weight (NEW) | 7-3 |
| 7.3.4 Evacuation/Protective Distance | 7-4 |
| 7.3.5 Discovery and Transport from Site to IHF | 7-5 |
| 7.3.6 NOSE Distance or Public Withdrawal Distance | 7-5 |
| 7.3.7 Public Notification | 7-5 |
| 7.3.8 IHF Access Controls | 7-6 |
| 7.3.9 Multiple IHF Siting | 7-7 |
| | |
| 8.0 Ordnance and Explosives Transportation Plan Summary | 8-1 |
| 8.1 Procedures | 8-1 |
| 8.1.1 Discovery and Transport to Storage Area | 8-1 |
| 8.1.2 Packaging | 8-1 |
| 8.1.3 Manifesting/Placards | 8-1 |
| 8.1.4 Off-site Selection | 8-2 |
| 8.2 Emergency Response | 8-2 |
| 8.2.1 Incident Containment and Controlling of Hazardous Waste | 8-2 |
| 8.2.2 Hazardous Materiel Reporting Procedures | 8-3 |
| 8.2.3 Military EOD participation | 8-4 |
| | |
| 9.0 RCWM Transportation Plan Summary | 9-1 |
| 9.1 Discovery and Transport to IHF | 9-1 |
| 9.1.1 Packaging | 9-2 |
| 9.1.2 Manifesting | 9-2 |
| 9.1.3 Placarding | 9-2 |
| 9.2 Off-Site Transportation | 9-3 |

DID OE-070.01

Attachment A Outline for RCWM Safety Submission (CSS)

| | |
|---|------|
| 10.0 Public Affairs Summary | 10-1 |
| 10.1 Restoration Advisory Board (RAB) | 10-1 |
| 10.2 Anomaly Review Board | 10-1 |
| 11.0 Engineering Controls Summary | 11-1 |
| 11.1 Brief description of what types will be used on project site, VCS, ECS, Filters, Blast mitigating devices and their effects on the safety distances for the MPM and the NOSE. Full technical details will be available on-site, or upon request , or included for “first-used” technology. | 11-1 |

List of Figures

| | | |
|------------|--|-----|
| Figure 1-1 | Explosives Siting Distances, Storage Site (QD Arcs) | 1-? |
| Figure 1-2 | Fragmentation Zones (QD Arcs) | 1-? |
| Figure 1-2 | Installation/Site Boundaries | 1-? |
| Figure 1-2 | NOSE Distances, 1% Lethality Distance | 1-? |
| Figure 1-2 | Areas Designated for Disposal of “safe-to-move” conventional UXO | 1-? |
| Figure 6-1 | Wind Rose Data for Site | 6-? |

List of Tables

| | | |
|-----------|--|-----|
| Table 1.1 | NOSE Distances for MCE(s) | 1-? |
| Table 1.2 | Activity Hazard Analysis Table for all RCWM and Explosives-related tasks | 1-? |
| Table 2.1 | Analytical Methods | 2-? |
| Table 3.1 | Air Monitoring Matrix | 3-? |
| Table 4.1 | Personal Protective Equipment (PPE) Requirements by Task | 4-? |
| Table 4.2 | PPE Upgrade Criteria | 4-? |
| Table 4.3 | Decontamination Applications | 4-? |
| Table 4.4 | Personnel Decontamination Procedures | 4-? |