

CONSTRUCTION/TARGET INTERFACE QUALITY ASSURANCE

For the Combined Arms Collective Training Facility (CACTF)

The Range Project Construction Checklists are provided for use by personnel involved in construction quality oversight, specifically for assurance of target equipment and instrumentation interface. It is a checklist of common items which should be verified during construction phase of a range project. Two inspections are mandated by AR 350-19; a Construction Compliance Inspection (CCI) when construction is approximately 50% complete and a Target Interface Inspection (TII) when all target and instrumentation equipment interface points have been completed (approximately 95% construction completion).

DESIGN PHASE: The construction contractor must be made aware of the impending inspections. It is advised that they be discussed at the preconstruction conference with provision of the CCI/TII checklist. The inspections should also be included in a Division 01 section of the construction contract specifications. The Quality Control section is the recommended location; however a separate specification section may be inserted to address other Government inspection and quality assurance issues. Suggested CCI/TII specification verbiage is provided below:

3.1 CONSTRUCTION COMPLIANCE INSPECTION (CCI)

The Government will perform a Construction Compliance Inspection (CCI) to assess construction progress and to identify problem areas with target interface items early to avoid costly and extensive corrective actions and project delays at the Target Interface Inspection (TII). Target interface items include all portions of construction that physically connect to the target equipment or provide for the protection of the equipment. The US Army TRADOC Program Integration Office (TPIO-Live) will schedule the CCI in conjunction with the RTL P MCX (HNC), the applicable Corps of Engineers District, PEO-STRICOM, and the installation, and the Major Command (MACOM) when construction has reached the point that the following items can be checked (usually about midpoint of construction). A minimum of one training building shall be complete, including the installation of all electrical power equipment, all data equipment including power and data cables and conduits. In all cases, the data termination racks and samples of the power and data cables and associated connectors shall be on site and available for inspection, but they do not have to be installed. In the control building Range Operations Center (ROC), space shall be shown for the master data panel(s) and cable trays or wireways for routing cables to range operating system(s). A CCI Checklist has been developed to conduct this inspection. Any “required” items noted during the CCI shall be corrected prior to continuing to the next phase all other items shall be corrected in a timely manner.

3.2 TARGET INTERFACE INSPECTION (TII)

The Government will perform a Target Interface Inspection (TII) when all target equipment interface points are completed and ready for inspection (usually around 90 – 95 percent construction completion or about 30 days prior to the end of construction).

The US Army TRADOC Program Integration Office (TPIO-Live) will schedule the TII in conjunction with the RTLP MCX (HNC), the applicable Corps of Engineers District, the installation, the MACOM, PEO-STRICOM, and the target installation contractor. All training buildings shall be complete, including the installation of all electrical power equipment, and all data equipment including power and data cables and conduits. Power cables shall be connected to all associated electrical equipment and tested. At the target emplacement locations and data termination racks, data cables shall be terminated/connected and tested. At the ROC, fiber data cables shall be terminated/connected in the data termination rack (DTR) and tested. Cable tray(s) or wireway(s) for routing cables to range operating system(s) shall be installed. 120V, 20A circuits shall be installed near the locations for the master data panels (OPA installed) and the data termination rack. A TII Checklist has been developed to conduct this inspection. Any items noted during the TII shall be corrected prior to closeout of the construction contract.

INSPECTION CHECKLIST AND PROCEDURES: The overall inspection checklist consists of segments for components of the range and, in some cases, segmented specific to a range type. The components and/or range specific range type list that apply to a particular range project will be utilized for both the CCI and TII inspections. The checklist user should mark the “YES” or “NO” block after each item and write clarifying remarks in the “NOTES” column when appropriate. Items marked “NO” must be corrected or resolved prior to project continuation to the next phase.

Proposed users of the Construction checklist are identified but not limited to those shown below:

<i>Purpose:</i>	<i>Users:</i>
Construction Compliance	COE and Subcontractors/Inspection Contractors
Construction Compliance	TPIO-L Personnel
Construction Compliance	PEO-STRI
Target Interface	COE and Subcontractors/Inspection Contractors
Target Interface	ATSC Personnel
Target Interface	PEO-STRI and Supplier/Contractor
Target Interface	MACOM

The checklist is designed to be a quality assurance guide only and is not intended to replace Army publications (ARs, TCs, FMs CEHNC 1110-1-23) which address key aspects of the Sustainable Range Program. TPIO-L personnel will use the checklist in conjunction with the construction phase of assigned range projects. A copy will be used and attached to the formal MFR Target Interface Inspection Deficiencies List which results from all interface inspections. Designated post/installation personnel are encouraged to use it throughout the developmental cycle of each approved range project.

TPIO-L schedules the Construction Compliance Inspection (CCI) and the Target Interface Inspection (TII) during the construction phase of an RTLP project. Guidance for determining when these inspections should be scheduled is as follows:

a. CCI: The inspection should take place when construction has reached the point that a minimum of one training building is complete, including the installation of all electrical power equipment, all data equipment including power and data cables and conduits. The

data termination racks and samples of the power and data cables and associated connectors shall be on site and available for inspection, but they do not have to be installed. In the control building Range Operations Center (ROC), space shall be shown for the master data panel(s) and cable trays or wireways for routing cables to range operating system(s)

b. TII: The range is ready for the TII when all targetry and instrumentation interface points are complete and ready inspection (usually around 90-95 percent construction completion or about 30 days prior to the end of construction).

TARGETRY INSTALLATION: A range is ready for targetry installation when all deficiencies noted during the TII have been corrected and TPIO-L has been notified. The installation contractor must have unrestricted access to the range during installation