

## CONSTRUCTION/TARGET INTERFACE QUALITY ASSURANCE

For the Shoothouse

The Range Project Construction Checklists are provided for use by personnel involved in construction quality oversight, specifically for assurance of target equipment and instrumentation interface. It is a checklist of common items which should be verified during construction phase of a range project. Two inspections are mandated by AR 350-19; a Construction Compliance Inspection (CCI) when construction is approximately 50% complete and a Target Interface Inspection (TII) when all target and instrumentation equipment interface points have been completed (approximately 95% construction completion).

**DESIGN PHASE:** The construction contractor must be made aware of the impending inspections. It is advised that they be discussed at the preconstruction conference with provision of the CCI/TII checklist. The inspections should also be included in a Division 01 section of the construction contract specifications. The Quality Control section is the recommended location; however a separate specification section may be inserted to address other Government inspection and quality assurance issues. Suggested CCI/TII specification verbiage is provided below:

### *3.1 CONSTRUCTION COMPLIANCE INSPECTION (CCI)*

*The Government will perform a Construction Compliance Inspection (CCI) to assess construction progress and to identify problem areas with target interface items early to avoid costly and extensive corrective actions and project delays at the Target Interface Inspection (TII). Target interface items include all portions of construction that physically connect to the target equipment or provide for the protection of the equipment. The US Army TRADOC Program Integration Office (TPIO-Live) will schedule the CCI in conjunction with the RTLTP MCX (HNC), the applicable Corps of Engineers District, PEO-STRICOM, and the installation, and the Major Command (MACOM) when construction has reached the point that the following items can be checked (usually about midpoint of construction).*

*At a minimum:*

- *Data Enclosure is mounted in Shoothouse electrical room.*
- *The lighting contactor and panelboard mounted in Shoothouse electrical room.*
- *The power and data outlets (UTO) to one target location mounted in Shoothouse area.*
- *Provisions should be shown in the Shoothouse for routing of the power and data cables to the UTO locations from the electrical room data enclosure.*
- *Provisions should be shown in AAR for routing data cables from the data termination rack throughout the AAR.*
- *Wireway (conduit) routed for fiber cable from underground into the data enclosure at the Shoothouse and data termination rack in AAR.*
- *Provide samples of SC type connector, fiber optic cable, and cat6 cable.*
- *The AAR should have the data termination rack on-site and the location identified within the AAR.*

A CCI Checklist has been developed to conduct this inspection. Any “required” items noted during the CCI shall be corrected prior to continuing to the next phase all other items shall be corrected in a timely manner.

### 3.2 TARGET INTERFACE INSPECTION (TII)

The Government will perform a Target Interface Inspection (TII) when all target equipment interface points are completed and ready for inspection (usually around 90 – 95 percent construction completion or about 30 days prior to the end of construction). The US Army TRADOC Program Integration Office (TPIO-Live) will schedule the TII in conjunction with the RTLP MCX (HNC), the applicable Corps of Engineers District, the installation, the MACOM, PEO-STRICOM, and the target installation contractor.

At a minimum:

- Power is turned on to the AAR and Shoothouse site.
- All items such as the data enclosure, lighting contactor, UTO (power and data), fiber cabling, data cabling, power cabling, wireways(conduits), lightning protection, and grounding for the Shoothouse is complete.
- All items such as the data termination rack, wireways(cable trays/conduits), power to the DTR, lightning protection, and grounding for the AAR is complete.
- HVAC in AAR is located and on-site or installed to determine size.

A TII Checklist has been developed to conduct this inspection. Any items noted during the TII shall be corrected prior to closeout of the construction contract.

**INSPECTION CHECKLIST AND PROCEDURES:** The overall inspection checklist consists of segments for components of the range and, in some cases, segmented specific to a range type. The components and/or range specific range type list that apply to a particular range project will be utilized for both the CCI and TII inspections. The checklist user should mark the “YES” or “NO” block after each item and write clarifying remarks in the “NOTES” column when appropriate. Items marked “NO” must be corrected or resolved prior to project continuation to the next phase.

Proposed users of the Construction checklist are identified but not limited to those shown below:

<i>Purpose:</i>	<i>Users:</i>
Construction Compliance	COE and Subcontractors/Inspection Contractors
Construction Compliance	TPIO-L Personnel
Construction Compliance	PEO-STRI
Target Interface	COE and Subcontractors/Inspection Contractors
Target Interface	ATSC Personnel
Target Interface	PEO-STRI and Supplier/Contractor
Target Interface	MACOM

The checklist is designed to be a quality assurance guide only and is not intended to replace Army publications (ARs, TCs, FMs CEHNC 1110-1-23) which address key

aspects of the Sustainable Range Program. TPIO-L personnel will use the checklist in conjunction with the construction phase of assigned range projects. A copy will be used and attached to the formal MFR Target Interface Inspection Deficiencies List which results from all interface inspections. Designated post/installation personnel are encouraged to use it throughout the developmental cycle of each approved range project.

TPIO-L schedules the Construction Compliance Inspection (CCI) and the Target Interface Inspection (TII) during the construction phase of an RTLP project.

**TARGETRY INSTALLATION:** A range is ready for targetry installation when all deficiencies noted during the TII have been corrected and TPIO-L has been notified. The installation contractor must have unrestricted access to the range during installation