ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR MATERIAL	FLOOR FINISH	BASE MATERIAL	BASE FINISH	WALLS A WALL MATR'L	WALLS A WALL FINISH	WALLS B WALL MATR'L	WALLS B WALL FINISH	WALLS C WALL MATR'L	WALLS C WALL FINISH	WALLS D WALL MATR'L	WALLS D WALL FINISH	CEILING MATERIAL	CEILING FINISH	CEILING HEIGHT	REMARKS
101	AISLE	CONC	1	CONC	1	MTPL	3	CONC	2	MTPL	3	MTPL	3	MTPL	3	VARIES	
102	AISLE	CONC	1	-	0	MTPL	3	CONC	2	-	0	MTPL	3	MTPL	3	VARIES	
103	AISLE	CONC	1	-	0	-	0	CONC	2	MTPL	3	MTPL	3	MTPL	3	VARIES	
104	STORAGE CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	11'- 0"	
105	STORAGE CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	11'- 0"	
106	STORAGE CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	11'- 0"	
107	STORAGE CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	11'- 0"	
108	STORAGE CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	11'- 0"	
109	STORAGE CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	11'- 0"	
110	INSPECTION BAY	CONC	1	CONC	1	-	0	CONC	2	-	0	CONC	2	MTPL	3	VARIES	
111	INSPECTION BAY	CONC	1	CONC	1	-	0	CONC	2	-	0	CONC	2	MTPL	3	VARIES	
112	TEST CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	10'- 0"	
113	INSPECTION BAY	CONC	1	CONC	1	-	0	CONC	2	-	0	CONC	2	MTPL	3	VARIES	
114	TEST CUBICLE	CONC	1	CONC	1	CONC	2	CONC	2	CONC	2	CONC	2	CONC	2	10'- 0"	
115	INSPECTION BAY	CONC	1	CONC	1	-	0	CONC	2	-	0	CONC	2	MTPL	3	VARIES	
116	INSPECTION BAY	CONC	1	CONC	1	-	0	CONC	2	-	0	CONC	2	MTPL	3	VARIES	
117	INSPECTION BAY	CONC	1	CONC	1	-	0	CONC	2	-	0	CONC	2	MTPL	3	VARIES	
118	BAY SUPPORT	CONC	8	RUBR	5	GYBD	6	GYBD	6	GYBD	6	CONC	6	EXPO	7	VARIES	NOTE 4
119	BREAKROOM	CONC	8	RUBR	5	GYBD	6	GYBD	6	GYBD	6	CONC	6	EXPO	7	VARIES	NOTE 4
120	TOOL STORAGE	CONC	8	RUBR	5	GYBD	6	GYBD	6	GYBD	6	CONC	6	EXPO	7	VARIES	NOTE 4
121	CORRIDOR	CONC	8	RUBR	5	GYBD	6	CMU	6	GYBD	6	GYBD	6	EXPO	7	VARIES	NOTE 8
122	MECHANICAL ROOM	CONC	8	NONE	0	CMU	0	CONC	0	CONC	0	CMU	0	EXPO	0	VARIES	
123	WOMEN	TILE	9	TILE	9	CMU	11	CONC	11	CMU	11	CMU	11	EXPO	7	VARIES	NOTE 4
124	JAN CLOSET	CONC	8	NONE	0	CMU	11	CMU	11	CMU	11	CMU	11	EXPO	7	VARIES	NOTE 4
125	MEN	TILE	9	TILE	9	CMU	11	CONC	11	CMU	11	CMU	11	EXPO	7	VARIES	NOTE 4
126	SUPPLY ROOM	CONC	8	RUBR	5	GYBD	6	GYBD	6	CMU	6	CMU	6	EXPO	7	VARIES	NOTE 4

NOTES:

1. METAL TOILET PARTITIONS TO BE GLOBEL STEEL PRODUCTS CORP. TAN 1022 BAKED ENAMEL, OR EQUAL.
2. LAMINATED PLASTIC TO BE FORMICA DESERT BEIGE DESIGN-099-65 FINISH, OR EQUAL.
3. COLORS LISTED ARE FOR COLOR INDENTIFICATION ONLY. LISTING IS NOT INTENDED TO LIMIT SELECTION OF SIMILIAR COLORS FROM OTHER MANUFACTURERS.
4. ALL SURFACES, EXCEPT SPRINKLER HEADS, ABOVE THE 8'-0" LINE SHALL BE PAINTED COLOR NO. 37038. (BLACK)
5. EXCEPT IN THE SUPPORT BAY AREA, ALL STRUCTURAL STEEL, INCLUDING BEAMS, COLUMNS, AND JOISTS, SHALL BE PAINTED COLOR NO. 22199. (ORANGE)
6. ALL GUTTERS, DOWNSPOUTS, EXTERIOR STRUCTURAL MEMBERS, AND FASCIA TRIM SHALL BE PAINTED COLOR NO. 12199. (ORANGE)
7. OUTSIDE SURFACES OF LOUVERS AND EXHAUST FAN DAMPERS SHALL BE COLOR NO. 20095.(BROWN)
8. PIPES TO BE PAINTED CONTINUOUS WITH PRIMARY COLOR. SEE SPEC. FOR COLOR CODES.

FINISH SCHEDULE CODES

0 NOT APPLICABLE
1 CONDUCTIVE/SPARKPROOF- COLOR NO. 37038.(BLACK)
2 RUBBED CONCRETE
3 PREFINISHED (GALVANIZED ALUMINUM)
4 NOT USED

5 BASE COLOR - 20095 (BROWN)
6 COLOR NUMBER - 27769 (TAN)
7 COLOR NUMBER - 37038 (BLACK)
8 SEALED CONCRETE/STAINED, COLOR - 36293 (GRAY)
9 TILE COLOR - UNITED STATES CERAMIC TILE CO., Q-3306001 ANTIQUE, 2X2 CERAMIC MOSAIC TILE.
10 NOT USED
11 COLOR NUMBER - 20095 (BROWN)

Symbol	Description	Date	Approved
	Revisions		

US ARMY ENGINEER DIVISION HUNTSVILLE
CORPS OF ENGINEERS
HUNTSVILLE, ALABAMA

Site adapt A/E :

US Army Corps of Engineers

STANDARD DESIGN
AMMUNITION SURVEILLANCE FACILITY
ROOM FINISH SCHEDULE

Dwn. by : LM | Ckd. by : LM

Reviewed by : JFS | Date : | Sheet reference number : A-11 | Design file no.: | Rev.

Approved by : | Drawing code : STD 216-12-01 | Sheet of